




ROLL-IN RACKS RETARDER PROVER FOR FRESH DOUGH 1 CHAMBER OF 3 RACKS 670 X 810 - INLET 670 MM LUXE VERSION - L LAYOUT

No contractual pictures



DESCRIPTION

- Isothermal panels constituted of polyurethan foam, 50mm thick, density 35kg/m³, high insulation coefficient Lambda=0,022
- Outside is pre-enamelled
- Inside and front are made of STAINLESS STEEL
- Complet air flow on the length of the prover
- Resin basement included
- Door hinges on the right hand side (standard fitting)
- Lighting
- Electrical defrosting
- Regulation: FPCHR electronic control board with humidity controled by boiler
- Adjustable heating power
- Remote compressor
- Delivered dismantled
- Racks not supplied

OPTIONS

- External panels made of STAINLESS STEEL
- Condensing unit on roof
- Double door
- Additionnal door for "Tunnel" arrangement
- Window

Width	Depth	Height	Opened door depth	Door passage	Net Weight	Electrical Supply	Absorbed power	Absorbed current
2505 mm	1239 mm	2230 mm	2039 mm	700 mm	537 kg	400V TRI 50Hz	2.4 KW	6.5 A
Cold power -10/+32°C		Heating power	Boiler power (option)	Defrosting power (option)	Cooling fluid	Cooling fluid load		
1.1/8 CV	1887 W	1500 W	800 W	W	R404A	1.5 kg		

WARNING : Save available height : 100 mm above the top or 500 mm if cold unit located on the top.
In case of double door, remove "100 mm + half of door passage" on opened door depth dimension.
For overall depth, add 120 mm corresponding to the electrical control board.